

The Tinkerer's Manual

How to program Gaussian splats: what one splat is, how the toys are built, and a small language for writing your own splat equations, and toys that show pictures and read what you type.



Every toy in [Splashery](#) is made of Gaussian splats: tens of thousands of soft, colored blobs that blend into a solid-looking thing. This manual is for anyone who knows some math and wants to make splats do what they say. It goes level by level. You can stop after any level and still have something to play with.


Contents

1. [Level 1: What a splat is](#)
2. [Level 2: How a toy is built](#)
3. [Level 3: The splat equation language](#)
4. [Level 4: A gallery of programs](#)
5. [Level 5: Pictures, screens and your own input](#)
6. [What else Splashery does now](#)
7. [What comes later: Code a toy](#)
8. [Glossary](#)
9. [Further reading](#)
10. [Quick reference](#)

LEVEL 1

What a splat is


A **splat** is a small cloud of color floating in space. Up close it looks like a soft ellipse, bright in the middle and fading at the edges. On its own it is nothing much. Put thousands side by side and they melt into surfaces: a torus, a seashell, a cat.



100 splats



400 splats



6,000 splats

The same sphere with more and more splats, made with the Splat equation toy. With few splats you see each soft blob; with enough of them, they blend into one smooth surface.

What is a 3D Gaussian?

Think of a smooth weight field centered at a point μ . Three positive widths and a rotation shape it: the places where the weight is equal form nested ellipsoids. The weight G is 1 at the center and falls off with distance measured in units of those widths. To draw one, the renderer flattens the field into an elliptical patch on the screen, gives it a color, and blends its opacity over the patches behind it. A splat is not a surface of triangles and not a rigid little ball. Here G peaks at 1, so it is a weight, not a probability density (which would be scaled to add up to 1).

Three ways splats come to exist (Figure 1). Do not mix them up:

- **A recipe's placed splats.** A toy's recipe places them by rule: points sampled on the kit's shapes, each given a size, a rotation and a color. Nothing is fitted to photos.
- **A trained capture.** A splat file made by other software from many photos of a real thing, then opened here (`.ply` , `.sog` , `.splat` or `.spz`). The page shows these; it does not train them.
- **The one-photo teaching fit.** The Gaussian splatting toy fits flat, 2D Gaussians to a single picture by gradient descent. It shows the fitting idea; it is not a 3D reconstruction.

A · A recipe places them

kit shapes + color functions + a seed
→ points sampled on the shapes → splats

B · A trained capture

photos from many angles → training by other software
→ a `.ply`, `.sog`, `.splat` or `.spz` file you open

C · The one-photo teaching fit

one picture → flat 2D Gaussians fitted by
gradient descent, shown by the Gaussian splatting toy



The viewer sorts and blends the splats

projection, then back-to-front blending (Figure 2)

Figure 1. Three different things are called "splats". Only the first two make a 3D object; the third fits a flat picture.

The numbers in one splat

Each splat is described by a handful of numbers:


Part	Numbers	What it means
Center μ	3: x, y, z	Where the middle of the splat is.
Sizes s	3: s_1, s_2, s_3	How far it spreads along each of its own three axes. Equal sizes make a ball; one small size makes a flat disc.
Rotation q	4 (a quaternion)	Which way those three axes point.
Color	3: red, green, blue	Each from 0 to 1.
Opacity α	1	How solid its middle is, from 0 (clear) to 1 (solid).

That is 14 numbers per splat. A kit toy starts with a budget of 60,000 splats at the Low tier, 140,000 at Mid, 200,000 at High and 280,000 at Max. Recipes can raise that budget, up to 400,000 at Max. Auto picks Low, Mid or High; Max is a viewer choice. Many splat files also let a splat's color change a little with the direction you look from; the toys you build here use one color per splat.

The Gaussian: a bell in three dimensions

The "Gaussian" in Gaussian splat is the bell curve, named after the mathematician Carl Friedrich Gauss. In one dimension, a bell centered at μ with width σ (sigma, the standard deviation) is

$$G(x) = \exp(-(x - \mu)^2 / 2\sigma^2)$$



The bell curve. At one σ from the center it has fallen to about 0.61, at two σ to about 0.14, and at three σ to about 0.01, so a splat fades out within about three of its sizes.

In three dimensions the width becomes a 3-by-3 matrix Σ (capital sigma), called the **covariance**, and the squared distance becomes a quadratic form. For a point p in space, the splat's strength there is

$$G(p) = \exp(-\frac{1}{2} (p - \mu)^T \Sigma^{-1} (p - \mu))$$

Where G is the same value, you are on the same "shell" around the center, and those shells are ellipsoids: stretched and turned spheres.


Approximation: the drawn bell is finite. The ideal G never reaches zero. The site's renderer cuts each splat off where G has fallen to e^{-4} , about 0.02 (a little under 3 sizes out), and rescales the falloff so it reaches exactly 0 there. A labs-only setting can swap in a sharper falloff for one toy. So the equations here describe the ideal splat, and the screen shows a close, cut-off copy of it.

The covariance, built from sizes and a rotation

Not every 3-by-3 matrix is a valid covariance. It has to be symmetric, and it has to be positive definite (the bell must fall off in every direction). Instead of picking its nine numbers directly, a splat builds it from its three sizes and its rotation:

$$\Sigma = R S S^T R^T, \text{ where } S = \begin{pmatrix} s_1 & 0 & 0 \\ 0 & s_2 & 0 \\ 0 & 0 & s_3 \end{pmatrix}$$

and R is the rotation matrix of the quaternion q . Read it right to left, as a recipe for a shape: start with a round ball of size 1, stretch it by s_1 , s_2 and s_3 along x , y and z , then turn it by R . Any sizes above zero and any rotation give a valid covariance, which is exactly what you want when a computer is nudging millions of numbers.



A covariance from sizes and a rotation, drawn in two dimensions: a round splat is stretched along its own axes, then turned.

A worked example. Take sizes 0.3, 0.1 and 0.1, turned 30° about the z axis. Then SS^T has 0.09, 0.01 and 0.01 on its diagonal, and multiplying out $R SS^T R^T$ gives

$$\Sigma \approx \begin{pmatrix} 0.070 & 0.035 & 0 \\ 0.035 & 0.030 & 0 \\ 0 & 0 & 0.010 \end{pmatrix}$$

The top-left number is $0.09 \cos^2 30^\circ + 0.01 \sin^2 30^\circ = 0.07$, and the ones beside it are $(0.09 - 0.01) \sin 30^\circ \cos 30^\circ \approx 0.035$. Those off-diagonal numbers are the tilt.

From 3D to the screen

To draw a splat, the renderer works out what its bell looks like from the camera. It first turns the covariance into the camera's view, with the camera's rotation W . The perspective of a camera is not a straight-line map, but close to one point it nearly is, and its best straight-line stand-in there is a matrix J (the Jacobian of the projection). Then the splat's covariance on the screen is

$$\Sigma' = J W \Sigma W^T J^T$$

keeping only its top-left 2-by-2 block. That 2-by-2 matrix is a flat bell on the screen: an ellipse. Its eigenvectors are the directions of the ellipse's axes, and the square

roots of its eigenvalues are how far it spreads along them. This trick comes from EWA splatting (Zwicker, Pfister, van Baar and Gross, 2001).

Approximation: affine around the center. J is exact only at the splat's center, where the straight-line stand-in touches the true perspective map. Across the rest of the splat the real map bends away from it, so the ellipse is the first-order answer, not an exact image of the 3D bell.

Sorting and blending, back to front


Splats are see-through at their edges, so the order they are drawn in matters. The splats are sorted by their centers' depth along the camera's view, and painted from the farthest to the nearest. At each pixel, a splat's strength there is its opacity times its bell, $a = \alpha G'$, and it is laid over what is already there:

$$C \leftarrow a c + (1 - a) C$$

where c is the splat's color and C the pixel's color so far. Written out for all the splats at once, counting from the nearest ($i = 1$) to the farthest, the pixel's color over a black background is

$$C = \sum_i c_i a_i \prod_{j < i} (1 - a_j)$$

Each splat shows as much as the splats in front of it let through. This is how the 2023 paper that started the craze, "3D Gaussian Splatting for Real-Time Radiance Field Rendering" (Kerbl, Kopanas, Leimkühler and Drettakis), draws its scenes, and it is how Splashtery draws every toy.




Splats are painted from the back to the front, each one laid over the ones behind it.

Why the order matters in the toys. By default, Splashery sorts the splats in the pose a toy was built in, so a piece that moves keeps the order it had at rest. A recipe can request `out.resortPose` to sort moving parts and pages in their current pose. Turn a solid thing more than a quarter turn and its far side can be drawn over its near side. The toys work around it: the Splat equation toy, for one, builds its shape at twelve moments and morphs from the copy at the start of the current interval to the next (Level 3).

A worked example with a background. Take one color channel. The background is 0.2. The far splat (drawn first) has color 0.9 and strength $a = 0.5$ at this pixel. The near splat (drawn second) has color 0.1 and $a = 0.4$. After the far splat: $C = 0.5 \times 0.9 + 0.5 \times 0.2 = 0.55$. After the near one: $C = 0.4 \times 0.1 + 0.6 \times 0.55 = 0.37$. The same number comes from the sum above with the background added: $0.1 \times 0.4 + 0.9 \times 0.5 \times 0.6 + 0.2 \times 0.6 \times 0.5 = 0.37$. The share of the background that still shows, the **transmittance**, is $0.6 \times 0.5 = 0.3$.

Approximation: sorting uses centers. Each splat gets one depth, the depth of its center, so the order is per splat, not per pixel. Two big splats that overlap in depth can be drawn in the wrong order where they cross. This is why recipe authors keep layers apart (the recipe guide says splats "sort by their centers, so closer layers mix in stripes").

1 · Representation: a bell in space




- center μ : $G = 1$
- inner ring, 1σ : $G \approx 0.61$
- outer ring, 2σ : $G \approx 0.14$
- dashed, $\approx 2.8\sigma$: where the drawn bell stops ($G \approx 0.02$)


axes $s_1 s_2 s_3$, turned by the rotation q




2 · Projection: onto the screen



3D ellipsoid, Σ



$$J W \Sigma W^T J^T$$



elliptical footprint, $2 \times 2 \Sigma'$


J is a straight-line stand-in that is exact only at the center



3 · Blend: back to front

far: 1st

near: 2nd



$$C \leftarrow a \cdot c + (1 - a) \cdot C$$

order: by center depth;
what is left of the
background: transmittance

Figure 2. From a splat to a pixel. **1** The ideal bell has equal-weight shells; the drawn one is cut off. **2** The camera flattens the ellipsoid into an ellipse, using a straight-line stand-in for the perspective. **3** The ellipses are blended back to front, each over what is already there.

LEVEL 2

How a toy is built

Nobody places Splashery's splats by hand. Most toys are **recipes**: short programs that describe a toy with a kit of shapes, and the kit fills them with splats when you open the toy. A recipe is a few kilobytes of code instead of megabytes of splats, and because every random choice comes from a seed, it builds the same splats with the same seed, options and budget.

Recipes are written in JavaScript. This level is a tour, so you can read one; the complete guide is [docs/PACKS.md](#) in the source code.

Two places a toy lives

A toy's name and shelf go in a **catalog** entry (`src/toys.js`), and the toy itself in a **recipe** in a pack file (`src/packs/...js`):

```
{
  id: "little-windmill",      // lower-case words joined by hyphens
  label: "Little windmill",   // its name on the shelf
  category: "objects",        // which shelf
  kind: "kit",
  pack: "my-pack",            // loads src/packs/my-pack.js
}
```

A recipe has six basic parts, all optional except `build` (Level 5 adds `pictures` , `input` and `tiltLock` , and [PACKS.md](#) has more, such as `grab` and `drag` for touch play):

<code>build(k, o)</code>	Describes the toy with the kit <code>k</code> . <code>o</code> holds the chosen options.
<code>options</code>	Choices that rebuild the toy: a color, a style, a number of petals. They are saved in links.
<code>controls</code>	Live values from 0 to 1: sliders, toggles that ease on and off, and pulses that jump to 1 and fall back.
<code>action</code>	Which control a tap on the toy fires.
<code>drive(t, c, out)</code>	Runs every frame: from the time <code>t</code> and the controls <code>c</code> , it sets how the parts move.
<code>alive</code>	<code>true</code> when the toy moves by itself, so frames keep coming.

Shapes from the kit

`k.sphere(r)`, `k.ellipsoid(a, b, c)`, `k.box(w, h, d)`,
`k.roundedBox(w, h, d)`, `k.cylinder(r, h)`, `k.cone(r0, r1, h)`,
`k.torus(R, r)`, `k.disc(r)`, `k.lathe(profile)` (a vase or a bottle, turned around an axis), `k.tube(curve, radius)` (a stem, an arm, a knot) and
`k.param((u, v) => [x, y, z])`, any surface you can write in two variables (the same idea as Level 3; here u and v each run from 0 to 1), and
`k.radial((dir) => r)`, a blobby surface given by its distance from the middle in every direction. Nothing is drawn until you add a shape:

```
k.add(k.sphere(0.2), { pos: [0, 1, 0], color: "#ffcc33", weight: 2 });
```

The kit shares the splats out between the shapes by their surface area, so the toy is evenly dense; `weight` gives a small shape more (or `share` a fixed fraction of all the splats). For free-form splats, like stars, sparks and crumbs, `k.cloud` places them one by one. After `build`, the kit centers the toy and scales it to fit the view, so you can model in any units.

Colors from functions

A color can be a fixed one (`"#9c3b2c"`, or `[r, g, b]` with each from 0 to 1; there are no color names) or a function that the kit asks for every splat. It gets the splat's place `c.p`, its surface direction `c.n`, its surface coordinates `c.u` and `c.v`, and a random number and noise that come from the seed. Return `null` to leave a hole:


```
color: (c) => (c.p[1] > 0.5 ? "#ffffff" : "#3a7d44"), // snow above, grass below
```

Parts that hinge, spin or slide

A **part** is a group of shapes that moves as one solid piece: `k.part("lid", { pivot, axis })`. Every frame, `drive` tells each part where to be: an `angle` about its axis (a lid on a hinge, a wheel that spins), an `offset` (a drawer that slides), a `scale`, or `visible`. A toy may have up to 15 parts. The treasure chest's lid is a part on a hinge.



The treasure chest: its lid is a part on a hinge.



The graph plotter: the a slider is a control.

Behaviors

Some motion is too fine for parts: a flame that flickers, snow that falls, grass that sways. A **behavior** moves each splat on its own on the graphics card: `kind: "flame", "twinkle", "sway", "orbit", "fall", "wave"` and more. **Morphs** give each splat a second place, `to: (c) => [x, y, z]`, and slide it there as one of four channels goes from 0 to 1. The Splat equation toy's motion is made of morphs.

A small, complete recipe

Here is a whole toy: a little windmill whose sails turn with a Wind slider, and a tap that blows a gust, spinning them once more around.

```
import { mix } from "../src/kit.js";

// A little windmill: a stone tower, a red cap, and four sails that turn in
// the wind. A tap blows a gust that spins them once more around.
export const RECIPES = {
  "little-windmill": {
    alive: true,
    options: [{ key: "sails", label: "Sail color", type: "color", default: "#f2eee4" }],
    controls: [
      { key: "wind", label: "Wind", type: "slider", default: 0.4 },
      { key: "gust", label: "Gust", type: "pulse", ease: 3 },
    ],
    action: { key: "gust", label: "Blow a gust" },
  },
}
```

```

drive(t, c, out) {
  // The wind turns the sails; a gust adds one extra turn, eased in and
  // out, so they end where they would have been anyway.
  const g = c.gust > 0 ? 1 - c.gust : 0;
  const extra = 2 * Math.PI * g * g * (3 - 2 * g);
  out.parts.sails = { angle: t * (0.3 + 2 * c.wind) + extra };
},
build(k, o) {
  // The tower: whitewashed stone, darker toward the ground.
  k.add(k.cone(0.5, 0.3, 1.6), {
    color: (c) => mix("#8b8f97", "#ece6d8", (c.p[1] + 0.8) / 1.6),
    interior: 0.1,
    core: "#6b5b4b",
  });
  // The cap.
  k.add(k.cone(0.36, 0.02, 0.4), { pos: [0, 1.0, 0], color: "#9c3b2c" });
  // The sails turn together, about an axis that points at you.
  const sails = k.part("sails", { pivot: [0, 0.6, 0.42], axis: [0, 0, 1] });
  k.add(k.sphere(0.07), { pos: [0, 0.6, 0.42], part: sails, color: "#4b3a2a" });
  for (let i = 0; i < 4; i++) {
    const a = (i * Math.PI) / 2;
    k.add(k.box(0.16, 0.9, 0.02), {
      pos: [-0.5 * Math.sin(a), 0.6 + 0.5 * Math.cos(a), 0.44],
      rot: [0, 0, (a * 180) / Math.PI],
      part: sails,
      color: o.sails,
    });
  }
},
},
},
};

```



This recipe, built by the kit.



The Windmill on the shelf, a bigger toy built the same way.

Read it from the bottom up. `build` adds a cone for the tower (its color a function of height), a smaller cone for the cap, and a part called "sails" with a hub and four boxes, each turned a quarter turn more than the last. `drive` turns the sails part: steadily with the wind, plus one extra turn while the gust pulse runs, eased with the smoothstep curve $3g^2 - 2g^3$ so it starts and ends gently. A full extra turn lands the sails where they would have been anyway, so nothing jumps when the gust ends.

Run it yourself

You can run the windmill on your own computer in five steps. You need a copy of the Splashery source (download it from [GitHub](#)) and Python 3.

1. **Save the recipe as a pack.** Copy the module above into `src/packs/little-windmill.js`, or copy [manual/example-recipe.js](#). Change its first line to `import { mix } from "../kit.js";`. A pack lives in `src/packs/`, so the kit is one folder up. (The copy in `manual/` says `../src/kit.js` because it sits beside `src/`, not in it.)
2. **Add its catalog entry.** In `src/toys.js`, find the line `export const TOYS = [` and paste this right after it:

```
{
  id: "little-windmill",
  label: "Little windmill",
  category: "objects",
  kind: "kit",
  pack: "little-windmill",    // loads src/packs/little-windmill.js
},
```

The `id` must match the key in the pack's `RECIPES`.

3. **Serve the folder.** In the source folder, run `python3 -m http.server 8000 --bind 127.0.0.1`. The page needs a server because browsers will not load ES modules from a file address.
4. **Open the toy.** Go to `http://127.0.0.1:8000/embed/index.html?toy=little-windmill`. The embed page opens a catalog toy by its id. The windmill turns by itself.
5. **Tap the windmill.** The tap runs the recipe's action, the **Blow a gust** pulse: the sails spin one extra turn, easing in and out, and end where they would have been.

The Splat equation toy's text box takes equations (Level 3), not JavaScript recipes. A recipe has to be a module in `src/packs/`, as above.

LEVEL 3

The splat equation language


Recipes are powerful, but they are code, and code from a stranger can do things you did not ask for. The **Splat equation** toy on the math shelf gives you a smaller language that is only math. You write where every splat goes and what color it is, as equations, and nothing else can happen. That is why a link with your equations in it is safe to share.

Open it with any link in the gallery (Level 4). Type in the box under **Your own splat program** in the Toy tab and press **Splat it**. The Program list has eight famous shapes to start from.

The idea: every splat gets its own u and v

The toy lays out its splats on a grid of two numbers, u and v , each running over a range you choose. Your equations turn each splat's (u, v) into a place in space, (x, y, z) . If u goes around a circle and v around a smaller circle, the grid wraps into a torus:

```
x = (2 + cos v) * cos u
y = sin v
z = (2 + cos v) * sin u
u = 0 .. 2pi
v = 0 .. 2pi
```



Each dot on the grid is one splat with its own (u, v) . The equations carry every dot to its place on the torus.

The fields

A program is a list of **fields**, each written `name = value`. You can type one field or several, split by `;` (a text file can put one on each line). Any field you leave out

keeps what is showing.

Field	What it is	If left out
<code>x</code> , <code>y</code> , <code>z</code>	Where each splat goes, as equations in u , v and t . y points up.	Needed
<code>u</code>	The range of u , like <code>0 .. 2pi</code> .	Needed
<code>v</code>	The range of v .	<code>0 .. 1</code>
<code>hue</code>	Color as a place on the color wheel: 0 is red, 1/6 yellow, 1/3 green, 1/2 cyan, 2/3 blue, 5/6 magenta, and 1 is red again. Any number works; it wraps around every whole turn, so -0.1 gives the same hue as 0.9 .	Use r , g , b
<code>r</code> , <code>g</code> , <code>b</code>	Color as red, green and blue, each from 0 to 1. Setting any of them turns <i>hue</i> off; setting <i>hue</i> turns them off.	0.5 each (gray)
<code>size</code>	How big each splat is, in the same units as x , y and z : about the σ of its bell. It may use u , v and t .	<code>0.05</code>
<code>count</code>	How many splats: 100 to 10,000.	<code>4000</code>
<code>spread</code>	<code>grid</code> spaces the splats evenly; <code>random</code> scatters them at random over the ranges (a galaxy, a firework).	<code>grid</code>

You can also write `color` for `hue` , `red` , `green` and `blue` for `r` , `g` and `b` , `splats` for `count` , `x(u,v,t)` for `x` , and add notes after a `#` . Names can be in capitals or not. A range can be written `0 .. 2pi` , `0 to 2pi` or `0, 2pi` .

Expressions

The equations are read by the same small, safe reader as the Graph and Surface plotters. It understands:

- **Numbers:** `2` , `0.5` , `.25` .
- **Variables:** u , v and t . Range ends and the count are numbers only.
- **Constants:** `pi` (or π) and `e` .
- **Operators:** `+` `-` `*` `/` `^` , written `+` `-` `*` `/` `^` (and `**` , `.` , `^2` , `^3`), with brackets `( )` and `|u|` for absolute value.
- **Functions:** `sin` `cos` `tan` `asin` `acos` `atan` `sinh` `cosh` `tanh` `exp` `log` (natural; `ln` too) `log10` `sqrt` (or $\sqrt{}$) `abs` `floor` , and `min` and `max` of two or more values.

- **Shortcuts:** `2u` means $2 \times u$, `3sin(u)` and `(u + 1)(v - 1)` multiply, and a function can skip its brackets on a simple product: `sin 2u`, `cos v`.

Powers go first, then $\times$ and $\div$, then $+$ and $-$, and a power binds to the right: `2^3^2` is 2^9 , and `-u^2` is $-(u^2)$. Each field can be up to 120 characters long.

The grammar

For the curious, here is the core grammar. Words in quotes are typed as they are.

```

program    = field "=" value { ( ";" | new line ) field "=" value }
field      = "x" | "y" | "z" | "u" | "v" | "hue" | "r" | "g" | "b"
           | "size" | "count" | "spread"
value      = sum (x, y, z, hue, r, g, b, size)
           | sum ".." sum (u, v: numbers only)
           | sum (count: a number only)
           | "grid" | "random" (spread)
sum        = product { ( "+" | "-" ) product }
product    = signed { ( "*" | "/" ) signed | power } (nothing between: 2u)
signed     = { "-" | "+" } power
power      = atom [ "^" signed ]
atom       = number | "u" | "v" | "t" | "pi" | "e"
           | function "(" sum { "," sum } ")"
           | function atom { atom } (sin 2u)
           | "(" sum ")" | "|" sum "|"

```


Time

t is time. A tap on the toy plays it from 0 to 2π in about 4 seconds, and the **t** slider in the Toy tab holds it anywhere in between. Anything with t in it moves: `u + t` turns a shape, `sin(t)` breathes, and `sin(3u - t)` sends a wave around.

Behind the scenes, the toy builds your shape at 12 moments, $t = 0, \pi/6, 2\pi/6$ and so on, and each copy slides every splat in a straight line to its place in the next copy (a morph, Level 2), so every splat is at its computed place at those 12 moments (up to the packing error described below) and slides in a straight line in between. A shape that turns dips very slightly inward between moments, about 3 percent.

Approximations in time. The shape is sampled at 12 moments, not solved for every t . Only each splat's *position* slides toward the next copy, and that target is packed into 12 bits per axis over a fixed range, so tiny errors are possible. Its color, size and tilt are built separately for each copy, so they can step at a copy boundary instead of blending. The "count" you type is the number of points sampled for each copy, not the total number of splats in the toy (Figure 3).

One cycle of $t = 12$ stored copies



Where the splats go (the detail budget)

toy budget by device tier: Low 120,000 ·
Mid 240,000 · High 300,000 · Max 400,000

per copy: $\lfloor 0.98 \times \text{toy budget} \div 12 \rfloor$ (Low 9,800 ... Max 32,666)

points per copy: the smaller of count and that budget

Fine: up to $4 \times \text{count}$, still within the budget

grid rounds down; points with no value are dropped

Figure 3. A program with t is stored as 12 copies, so the number of splats in memory is about 12 times the points in one copy. The device's tier sets the budget at the top; your count, the Fine setting and the grid can only lower the points per copy.

Make it loop. Because t ends at 2π , a shape made of $\sin(t)$, $\cos(t)$ and angles like $u + t$ ends exactly where it began. A shape with plain t in it (like $y = t$) jumps back at the end. $\sin(t/2)$ goes out and back once; $\sin(2t)$ twice.

A program without t stands still. Then a tap clears it and draws the splats again one by one, in the order they are made: the first value of u with every v , then the next u , and so on.

What the toy does for you

- **It fits the view.** The shape at its sampled moments of t is scaled to fit, so your units don't matter; only the sizes compared with the shape do.
- **It spaces the grid.** With `spread = grid`, the side of the shape that is longer gets more splats, so they sit about evenly apart. A shape that uses only u is a curve, and

all the splats go along it.

- **It lights surfaces.** For a grid surface in Solid or Fine mode, each splat is a flat disc facing out from it (along the cross product of its slopes in u and v), lit from above. The **Light and shade** switch turns the lighting off, so you see your colors exactly. This is a simple shade, not physical lighting: your base color is multiplied by $0.62 + 0.48 \times$ (how squarely the disc faces a fixed light) and a small highlight is added.
- **It skips impossible points.** Where an equation has no value (the square root of a negative number, a division by zero), that splat is left out. So are points that shoot off far beyond the rest.
- **It explains mistakes.** Each field that can't be read gets one plain message, like “z: *That can't be drawn: I don't know “q”.*”, and the shape on the stage stays as it was.

Why it is safe

The reader never runs what you type. It breaks the text into numbers, the letters u , v and t , the names in the lists above and the signs, and builds a small tree of arithmetic from them. There is no way to name anything else, so the worst a program can do is draw a strange shape. Your program lives in the toy's link ("Copy link" in the Share tab), so you can send it to anyone.

LEVEL 4

A gallery of programs

The first eight are the toy's own programs; the rest are small ideas to copy and change. Each button opens the toy with that program; then tap it to play t . While the toy is being tried out, it is on the shelf only when Splashery is opened with `? labs=1`, but these links always open it.




Sphere

A sphere from two angles, u around and v from pole to pole, spinning with $u + t$. Six stripes from $\text{floor}(6u/(2\pi))$.

```
x = sin(v)cos(u + t)
y = cos(v)
z = sin(v)sin(u + t)
u = 0 .. 2pi
v = 0 .. pi
hue = floor(6u/(2pi))/6 + 0.04
size = 0.035
count = 7000
```

Open it in the toy



Torus

A tube around a ring. $v + t$ rolls the tube around itself, so it turns inside out as you watch.

```
x = (2 + cos(v + t))cos(u)
y = sin(v + t)
z = (2 + cos(v + t))sin(u)
u = 0 .. 2pi
v = 0 .. 2pi
hue = v/(2pi)
size = 0.09
count = 6000
```

Open it in the toy




Möbius strip

A band with a half twist: $\cos(u/2)$ turns the band over once as u goes around. The colors flow along it.

```
x = (1 + v cos((u + t)/2))cos(u + t)
y = v sin((u + t)/2)
z = (1 + v cos((u + t)/2))sin(u + t)
u = 0 .. 2pi
v = -0.4 .. 0.4
hue = u/(2pi)
size = 0.035
count = 4000
```

[Open it in the toy](#)



Seashell

A tube that grows by $\exp(0.1u)$ as it winds three times around, turning with $u + t$. Its splats grow too.

```
x = exp(0.1u)cos(u + t)(1.2 + cos v)
y = exp(0.1u)(sin(v) - 2.4) + 3
z = exp(0.1u)sin(u + t)(1.2 + cos v)
u = 0 .. 6pi
v = 0 .. 2pi
hue = 0.02 + 0.1u/(6pi) +
0.03cos(4u)
size = 0.14exp(0.1u)
count = 10000
```

[Open it in the toy](#)




Trefoil knot

The simplest real knot, a curve in u alone, turned about the vertical by the rotation formulas in t .

```
x = (sin(u) + 2sin(2u))cos(t) -
sin(3u)sin(t)
y = cos(u) - 2cos(2u)
z = -(sin(u) + 2sin(2u))sin(t) -
sin(3u)cos(t)
u = 0 .. 2pi
v = 0 .. 1
hue = u/(2pi)
size = 0.16
count = 2500
```

Open it in the toy



Wave

A flat sheet in u and v with ripples running out from the middle: $\sin(\text{distance} - t)$.

```
x = u
y = 0.45sin(2sqrt(u^2 + v^2) - t)
z = v
u = -3 .. 3
v = -3 .. 3
hue = 0.58 - 0.07sin(2sqrt(u^2 +
v^2) - t)
size = 0.07
count = 6000
```

Open it in the toy




Spiral galaxy

Two arms from $\text{floor}(v)$ (0 or 1, half a turn apart), scattered at random, turning once. Colors from r , g and b .

```
x = u^1.5 cos(pi floor(v) + 5u +
1.2(v - floor(v)) - t)
y = 0.06(1 - u)sin(91v + 37u)
z = u^1.5 sin(pi floor(v) + 5u +
1.2(v - floor(v)) - t)
u = 0.02 .. 1
v = 0 .. 2
r = 0.55 + 0.45(1 - u)^2
g = 0.62 + 0.33(1 - u)^2
b = 1 - 0.45(1 - u)^3
size = 0.006 + 0.012(1 - u)^2
count = 10000
spread = random
```

Open it in the toy



Klein bottle (figure eight)

The figure-eight Klein bottle: a figure-eight tube around a ring, with a half twist, so it has no inside or outside.

```
x = (2 + cos(u/2)sin(v + t) -
sin(u/2)sin(2v + 2t))cos(u)
y = sin(u/2)sin(v + t) +
cos(u/2)sin(2v + 2t)
z = (2 + cos(u/2)sin(v + t) -
sin(u/2)sin(2v + 2t))sin(u)
u = 0 .. 2pi
v = 0 .. 2pi
hue = v/(2pi)
size = 0.13
count = 8000
```

Open it in the toy



Hello, circle

The smallest program: one loop of u makes a ring of 200 splats. No v , no t .

```
x = cos(u)
y = sin(u)
z = 0
u = 0 .. 2pi
hue = u/(2pi)
size = 0.06
count = 200
```

[Open it in the toy](#)




Bouncing spring

Three turns of a helix whose height breathes with $\sin(t)$.

```
x = cos(u)
y = (0.09 + 0.035sin(t))u - 0.9
z = sin(u)
u = 0 .. 6pi
hue = 0.08 + u/(6pi)/3
size = 0.07
count = 1500
```

[Open it in the toy](#)



Beating heart

A famous heart curve, filled in by v from the middle out, beating twice per cycle.

```
x = v(1 + 0.08sin(2t))16sin(u)^3
y = v(1 + 0.08sin(2t))(13cos(u) -
5cos(2u) - 2cos(3u) - cos(4u))
z = 0
u = 0 .. 2pi
v = 0 .. 1
hue = 0.97 + 0.04v
size = 0.35
count = 4000
```

[Open it in the toy](#)




Rainbow ribbon

Color from r , g and b : three cosines about a third of a turn apart make a rainbow along u .

```
x = u
y = 0.4sin(2u - t)
z = v
u = -3 .. 3
v = -0.4 .. 0.4
r = 0.5 + 0.5cos(u)
g = 0.5 + 0.5cos(u - 2)
b = 0.5 + 0.5cos(u + 2)
size = 0.05
count = 4000
```

[Open it in the toy](#)



Firework

Splats scattered at random over a sphere (v is the height, from -1 to 1) fly out, droop and come back.

```
x = (0.2 + sin(t/2))sqrt(1 -
v^2)cos(u)
y = (0.2 + sin(t/2))v -
0.35sin(t/2)^2
z = (0.2 + sin(t/2))sqrt(1 -
v^2)sin(u)
u = 0 .. 2pi
v = -1 .. 1
hue = u/(2pi)
size = 0.018
count = 3000
spread = random
```

[Open it in the toy](#)




Opening flower

Five petals from $\cos(5u)$, and a cup that opens and closes with $\sin(t/2)$.

```
x = v(0.6 + 0.4cos(5u))cos(u)
y = (0.15 + 0.6sin(t/2))v^2
z = v(0.6 + 0.4cos(5u))sin(u)
u = 0 .. 2pi
v = 0 .. 1
hue = 0.92 - 0.12v
size = 0.035
count = 5000
```

[Open it in the toy](#)



Vase (no t)

A shape without `t` stands still, so a tap draws its splats again one by one, in the order they are made.

```
x = (0.5 + 0.2sin(3v))cos(u)
y = v
z = (0.5 + 0.2sin(3v))sin(u)
u = 0 .. 2pi
v = 0 .. 2.2
hue = 0.55 + 0.05sin(12u)
size = 0.045
count = 4000
```

[Open it in the toy](#)

Things to try. Change a number and see what moves. Swap `cos` and `sin`. Put `t` somewhere new. Make `count` small and `size` big to see the single splats. Try `spread = random` on a surface. Give a sphere a hue of `floor(8v/pi)/8`.

LEVEL 5

Pictures, screens and your own input

The toys in Level 2 are built from shapes. Some toys show something that is not a shape: a page of a PDF, a photo, a GIF, a video, or something you type or draw. Three additions to a recipe make them: **picture sheets**, an **input panel** and a few **view settings**. They are still Gaussian splats, all the way down. The toys on the Pictures and pages shelf are being tried out, so they are on the shelf only when Splashery is opened with `?labs=1`.

Picture sheets: a page, a photo, a GIF, a video

A **sheet** is a flat place in a toy where a picture shows: `k.sheet({ id, center, width, height })`. The kit draws nothing there. The site opens the picture before the build, then turns it into splats on the sheet after the build, in a background worker so the page stays smooth. A PDF page becomes a smooth sheet of large soft splats in the paper's color, with a small splat of its own color wherever the page differs from the paper, which is the ink (`method: "ink"`); in a photo, each sampled pixel becomes a flat splat (`"pixels"`); a GIF or a video becomes a screen that is redrawn on every frame (`"screen"`). The site picks the method from the kind of file. It rebuilds a sheet finer as you zoom in, and frees the pages you have left, so a book of 200 pages does not need 200 pages of splats.



A PDF page (the Picture lab)



The recipe below: a photo in a frame

Both pictures are made of splats. Photo: "Tulip field" by DennisM2, CC0. The article is our own sample text.

Three parts of a recipe work together:

- `pictures: { sample, accept }` names what shows until you open your own (the sample's address) and which kinds a visitor may open: `"pdf"`, `"image"`, `"gif"`, `"video"`.
- `drive` may choose the page of each sheet with `out.sheets[id] = { page, visible }`. Pages count from 0, and a page that does not exist shows nothing. A sheet that is not visible is not built unless it requests `ahead: 1`. Without it, every sheet shows the current page.
- `info.data.pictures` is the toy's view of the media: `page`, `count`, `kind`, `name`, `playing` and the functions `next()`, `prev()`, `go(n)` and `togglePlay()`.

A whole picture toy, in a few lines. Its `input` gives the Toy tab a button that opens a photo, a GIF or a video; the rest of the toy is a card and four wooden bars:

```
import { smoothstep } from "../src/kit.js";

// Two small picture toys for Level 5 of the Tinkerer's Manual: a framed photo
// that opens your own picture, and a little book whose page turns like paper.
export const RECIPES = {
  "little-frame": {
    turntable: false,
    tiltLock: true, // a drag only spins it left and right
    pictures: {
      sample: () => "assets/toys/picture-lab/photo.jpg", // shown until you open your own
```


```

    accept: ["image", "gif", "video"],
  },
  input: {
    title: "Your own picture",
    media: { accept: ["image", "gif", "video"] },
    note: "Open a photo, a GIF or a video. Files stay on this device.",
  },
  build(k) {
    // The picture: a sheet, filled with splats after the build.
    k.sheet({ id: "photo", center: [0, 0, 0.03], width: 1.5, height: 1 });
    // A gray card behind it, and four wooden bars around it.
    k.add(k.box(1.6, 1.1, 0.02), { pos: [0, 0, -0.02], color: "#9a9a9a" });
    for (const [w, h, x, y] of [
      [1.8, 0.1, 0, 0.6],
      [1.8, 0.1, 0, -0.6],
      [0.1, 1.1, -0.85, 0],
      [0.1, 1.1, 0.85, 0],
    ])
      k.add(k.box(w, h, 0.1), { pos: [x, y, 0], color: "#8a5a34" });
  },
},

```

Turning a page

A page that turns like paper is a sheet with `leaf: slot` (a slot from 0 to 9) and a spine to turn about: `k.spine({ at, axis, dir })` gives the spine's place, its direction, and the direction from it along the pages when they lie flat. Each frame, `drive` sets `out.leaves[slot] = { angle, curl }`: the `angle` in radians (0 lying flat, π turned all the way over) and the `curl`, how much the page bends along a circular arc (a negative number lets the free edge lag behind, like paper in air). Every splat of the page turns with the curve at its place, so it stays a solid sheet at every angle, which a page bent with soft regions would not.



The little book below, halfway through a turn. The next page is already there under the turning one.

The little book below uses a pulse control for the turn, the way Level 2's gust does. The page under the turning one is built ahead of time (a sheet is normally built only while it is visible, unless it requests `ahead: 1`, so a page that shows up halfway could make the turn wait), and the page number moves on when the turn ends. Keep a turning sheet on the body (part 0), because a part's own turn would replace the leaf's. The far side of the turning page shows the page in mirror image, like tracing paper, until it lands.

```
"little-book": {
  turntable: false,
  tiltLock: true,
  pictures: { sample: () => "assets/toys/picture-lab/article.pdf", accept: ["pdf"] },
  input: { title: "Your own book", media: { accept: ["pdf"] }, note: "Open a PDF." },
  controls: [{ key: "turn", label: "Turn the page", type: "pulse", ease: 1.2 }],
  action: { key: "turn", label: "Turn the page" },
  drive(t, c, out, info) {
    const pics = info.data?.pictures; // { page, count, go(n), next(), prev(), ... }
    // The page changes when the turn ends, and the turning page lands on the left.
    const turning = c.turn > 0;
    if (BOOK.turning && !turning && pics) pics.go(pics.page + 1);
    BOOK.turning = turning;
    const page = pics.page ?? 0;
    // The pulse falls from 1 to 0: the page swings from 0 to a half turn (pi)
    // about the spine, and its free edge lags behind, like paper.
    const s = turning ? smoothstep(0, 1, 1 - c.turn) : 0;
    out.leaves = [{ angle: Math.PI * s, curl: -1.2 * Math.sin(Math.PI * s) }];
    out.sheets = {
      // Once the turn starts, the left page is the one that is about to land on it.
      left: { page: turning ? page : page - 1 }, // a page out of range shows nothing
      under: { page: page + 1 }, // built ahead, and uncovered as the page lifts
      front: { page }, // the turning page (its far side shows in mirror image)
    };
  }
};
```

```

    // It is built, but hidden, until the turning page lands on it.
    out.parts.leftPage = { visible: turning ? 0 : 1 };
  },
  build(k) {
    BOOK.turning = false;
    k.spine({ at: [0, 0, 0], axis: [0, 1, 0], dir: [1, 0, 0] });
    const W = 1.4;
    const H = 1.9;
    const leftPage = k.part("leftPage");
    const page = { width: W, height: H };
    k.sheet({ id: "left", ...page, part: leftPage, center: [-W / 2, 0, 0], align: [1, 0] });
    k.sheet({ id: "under", ...page, center: [W / 2, 0, 0], align: [-1, 0] });
    // The turning page: a sheet on leaf slot 0, a hair in front of the others.
    k.sheet({ id: "front", ...page, center: [W / 2, 0, 0.008], align: [-1, 0], leaf: 0 });
    // The cover, behind the pages.
    k.add(k.box(2 * W + 0.1, H + 0.1, 0.03), { pos: [0, 0, -0.03], color: "#7a2f2f" });
  },
},
};


// Whether the page was turning in the last frame.
const BOOK = { turning: false };

```

Your own input: typing, drawing, opening a file

A recipe can ask for something from the visitor. Its `input` adds a panel to the Toy tab, in one of three forms:

- **Typing:** a text box and a button, and maybe a button that opens a text file (`fileButton` , `accept`). The Splat equation toy of Level 3 is one; so is the Word vectors toy, where you type *king – man + woman*.
- **Drawing:** `pad: { cols, rows, max, button }` adds a small grid you paint with a soft brush, and a button that hands the drawing to `read` as the text `"pad:..."` (one number for each cell, row by row). The CNN toy's "3D, draw a digit" view reads the digit you draw.
- **Opening a picture:** `media: { accept }` adds an **Open a file...** button, a field for a web address, the page buttons (or play and pause for a video) and a way back to the sample. Level 5's picture toys use it.



The input panel of a picture toy, in the Toy tab. Files are read on your device; nothing is uploaded.

For typing and drawing, `read(text, fileName)` turns what came in into option values, or throws an `Error` whose message the panel shows in place; and `shown()` says what is showing now. Keep what goes into options small: options are saved in the toy's link. Here is a whole toy with a typed input, a row of bars for the numbers you give it:

```
// A small toy with its own typed input, for Level 5 of the Tinkerer's Manual:
// type some numbers and the toy stands them up as bars.
const LIMIT = 12;
const COLORS = ["#e8384f", "#ffc233", "#1fb59a", "#4dabf7"];

export const RECIPES = {
  "little-bars": {
    options: [
      {
        key: "numbers",
        label: "Your numbers",
        type: "text",
        default: "3 1 4 1 5 9 2 6",
        hidden: true,
      },
    ],
    input: {
      title: "Your own numbers",
      placeholder: "3 1 4 1 5 9 2 6",
      button: "Show them",
      fileButton: "Open a text file...",
      accept: ".txt,.csv",
      note: `Type up to ${LIMIT} numbers from 0 to 20, separated by spaces or commas, or open a text
file with them.`,
      // Turns the typed text into option values, or throws a message that the panel shows.
      async read(text) {
        const list = String(text).match(/-?\d+(\.\d+)?/g) || [];
        if (list.length === 0) throw new Error("Type some numbers, like 3 1 4 1 5.");
        if (list.length > LIMIT) throw new Error(`That is more than ${LIMIT} numbers.`);
      }
    }
  }
}
```

```

    if (list.some((n) => n < 0 || n > 20)) throw new Error("Use numbers from 0 to 20.");
    return { numbers: list.join(" ") };
  },
  shown: () => "Your numbers",
},
build(k, o) {
  const values = String(o.numbers).split(" ").map(Number);
  values.forEach((v, i) => {
    const h = 0.05 + v / 10;
    k.add(k.box(0.14, h, 0.14), {
      pos: [(i - (values.length - 1) / 2) * 0.2, h / 2, 0],
      color: COLORS[i % COLORS.length],
    });
  });
},
},
};

```

The Screen and the Gaussian splatting toy


Two more toys put these to work: the Screen on the Pictures and pages shelf, and Gaussian splatting on the AI and computing shelf.

The **Screen** shows a video or a GIF on a screen in one of four styles: an old TV, a flat TV, a cinema with curtains and a hologram. Its picture is one sheet with `method: "screen"`; the knobs, the curtains and the glass are ordinary kit parts. A tap switches it on, and then plays and pauses; the speaker button in the top bar turns the sound on. You can open your own video or GIF.

The **Gaussian splatting** toy lets you watch how a photo becomes splats. Its **Training** view fits 2,400 flat (two-dimensional) Gaussians to a photo (a strawberry, or your own), by gradient descent in a background worker: the splats start as random specks and, step by step, they slide, stretch and change color until together they are the picture. The fit uses front-to-back blending, equivalent to the renderer's back-to-front blending, with the renderer's finite bell, so what you see is the real fit. **One splat** lets you set the sizes, the opacity and the color of a Gaussian illustrated by a cloud of small splats and turn it (Level 1's numbers); **Many splats** builds a small rubber duck from kit shapes and then shrinks every splat to a dot, so you see the splats that make it; and **Sorting** shows the splats of a ball appearing one by one, in the back-to-front order a camera draws them.




The Screen (old TV)



Gaussian splatting, training

Video frame from "Big Buck Bunny" © Blender Foundation, CC BY 3.0. Strawberry photo by Joselodos, CC0.



The One splat view: a Gaussian illustrated by small splats, with its three sizes drawn as axes (Level 1's s_1 , s_2 and s_3).

Steering the view: the top bar and the tilt lock

Three round buttons sit in the top bar, beside the sound and help buttons. They control how you look at the toy on show, and none of them changes the toy.



- **Reset view** (the circular arrow) puts the camera back where the toy starts. The **R** key does the same, and so does the button in the Tools tab. A double tap resets the view unless the toy uses it to focus on a page.
- **Tilt lock** (the padlock) makes a drag turn a toy only left and right, so a flat toy such as a page, a photo or a screen stays facing you. Zooming, panning and pinching still work. Your choice is remembered for that toy for the rest of your visit. In a recipe, it is the flag `tiltLock: true`, and every toy on the Pictures and pages shelf sets it. A link keeps the camera it was saved with, and the lock then holds that tilt.
- **Turntable** (the record player) switches the slow turn that a toy does when nobody is touching it. It is the same setting as **Turntable when idle** in the Toy tab, and this device remembers it. A recipe can opt out with `turntable: false`, as a page does. If your device asks for less motion, the turn stays off and the button is disabled.

Two fingers on a touch screen zoom. They roll the toy only after a clear twist (about 17 degrees) and turn it only when they move together, so a normal pinch never spins what you are looking at. A two-finger drag moves the toy across the screen instead of turning it, as do Shift or Option/Alt and a drag on a computer; **U** or **R** puts it back in the middle. A double-tap does too unless the toy uses it for page focus.

What else Splashery does now

This chapter lists what is on the site today, beyond the equation toy and picture toys you have read about. It describes only what is built. The **labs switch** hides newer parts until they are ready: add `?labs=1` to the site's address to turn it on (the browser remembers it; `?labs=0` turns it off). Each paragraph says what is behind it.

Hands-on physics

With the 🖐️ switch on, a drag picks up whatever is under your finger and a quick let-go tosses it. It lands, bounces and settles on the floor under the toy, inside an invisible play area, and soft toys squish when they land. The 🏠 button sends everything home. Every toy plays this way, scans included, as one rigid body; a recipe's `hands` block can instead make its pieces separate bodies, so a toy can have its own interactions. This is not behind the labs switch.

The QR code toy

The QR code toy makes a code from a link, plain text, a Wi-Fi network, a contact card or an email, and builds it from splats. Its motions (assemble, flip, burst and return, and an "alive" color wave) move each piece as a solid tile, and the alive wave keeps the gray values a reader sees unchanged, so each frame still scans. A "Scan view" turns the code flat to the camera, and after every change the toy renders that view and reads it back, to check that it scans. The reader is the browser's own detector where there is one, and otherwise the vendored jsQR library; nothing leaves the device. A Wi-Fi password is not kept in a link. This toy is behind the labs switch.

Captures and file formats

The viewer opens `.ply`, `.sog`, `.splat` and `.spz` files (version 4 SPZ files, which need a decoder Splashery does not ship, are refused with a message). Files can carry spherical harmonics, the view-dependent color the kit's splats do not use. The Scans shelf holds captures with their licenses and credits. The newer captures each ship as a full file and a lite file, and some keep a band of spherical harmonics on the full file. Many of the newer captures are behind the labs switch.

Camera, microphone and screen

A toy can read the microphone, the camera or a shared screen, but only after you tap a button for it. Nothing is requested before that tap. While a source is on, a small "Live" pill with a Stop button shows at the top of the page, and the sound or pictures stay on your device: nothing is recorded or sent. Two examples are the room echo meter (clap, and it measures how long the room rings) and the splat mirror (your camera as splats, with a depth model of about 27 MB that loads only after you start the camera). Both are behind the labs switch.

Books, albums and frames

Your book turns the pages of a PDF as paper: a page is a leaf with a front and a back, the engine can re-sort the splats of a turning page where it stands, and a turn waits until the next page is ready so it never shows a blank one. The words of a PDF page are available from its text layer, and links in the PDF are tinted on the page. The photo album opens several photos at once, and the picture frame lets you list them and move each up or down. These toys are behind the labs switch.

Studio: sound and photos

The Studio shelf turns other things into splats on your device. The song landscape makes a spectrogram of a song you open into a 3D field, and the Chladni plate shows sand finding a plate's still lines. Photo to 3D runs a depth model on your device, works out how far each part of a photo is, and rebuilds the photo as splats at their depths. The Studio toys are behind the labs switch.

Models to splats

The Model to splats toy opens a glTF or GLB file, an OBJ with its MTL, or an STL file and turns it into splats on your device: flat discs on the surface, more of them where there is detail, each sized to its neighbors so the surface closes, and colored from the model's texture, vertex colors or material. A toy's input can take several files at once, for a glTF with its `.bin` and textures. This toy is behind the labs switch.

Worlds

A world is a small place you walk around in, built on your device from recipes and a seed. It has a start screen, a list of places, collision, a character and a camera that follows. In splats mode everything you see is splats. In hybrid mode the ground, water, sky and signs are lit models, and only the props and the near grass stay splats, so "everything is splats" holds for the toys but not for every part of every world. Worlds are behind the labs switch (`worlds/?labs=1`).

Fluids, songs and smooth bodies

A recipe can declare a liquid, a gas or a flame with `k.fluid` . It is simulated while the toy is open and drawn as its own splats, one per particle, and the engine loads only when such a toy opens. A keyboard toy can play songs from its own list, a MIDI file or a tune pasted as ABC notation, with every key, hammer and string moving as a solid piece. Recipes can also join shapes into one smooth body and place one toy's recipe inside another's (the anatomy atlas does both). The Fluid lab, the bottle toys and the anatomy atlas are behind the labs switch.

Solid, Fine and Dots, and the detail you see

The Splat equation toy has three looks. **Solid** lays a surface's splats flat along it so they close into a clean shape, **Fine** uses up to four times as many smaller splats within the device's budget, and **Dots** shows each splat you programmed as its own round dot. The toy also asks for the sharper labs kernel. Beyond that toy, the viewer's Detail setting (Auto, High or Max) lives in your browser only, never in a link, and on every toy the canvas resolution drops while you drag if frames are slow. Those two are not behind the labs switch; the toy and the sharper kernel are.

The viewer's controls

Focus mode hides everything but the toy (the **F** key or the focus button, and **Esc** brings the rest back). On a computer, **I** folds the side panel and **G** opens the gallery. A toy's input panel can take a typed text, a drawing, a file, a binary file such as a sound, or several files at once. These controls are for everyone.

What comes later: Code a toy

The splat equation language can place and color splats, but it can't give a toy parts, controls or a tap of its own. For that you need a full recipe (Level 2). Splashery's plan includes a **Toy Workshop** where you will be able to write one: a **Code a toy** editor that builds and shows your recipe as you type.

Sharing those toys will work differently from sharing equations. A recipe is real JavaScript, and a page that ran a stranger's JavaScript straight from a link could be made to do things its visitor never agreed to. So a coded toy will be shared as a **submission**: it is checked and read by a person before it joins the shelf, the way every toy in Splashery is today. Equations stay the quick way to share; recipes are the deep one.

Until then, everything in Level 2 is in the source code, which is open under the MIT license: github.com/ryanjosephkamp/splashery.

Glossary

Gaussian (peak-one bell)

A smooth weight that falls off exponentially with the squared distance from a center, measured in units of the widths. In this manual it peaks at 1.

Mean, center μ

The position where the bell has its largest weight.

Standard deviation, axis width s

A length that measures distance along one of a splat's own axes. It is a yardstick, not a hard radius: the ideal weight is still about 0.14 at two widths.

Covariance Σ

A symmetric 3-by-3 matrix that holds the squared widths and the way the axes are turned, $\Sigma = R S S^T R^T$. Terms off the diagonal mean the axes are tilted.

Anisotropic, isotropic

Different widths along the axes, or equal widths in every direction. A plain kit splat is isotropic; the flat discs that cover a surface are anisotropic.

Quaternion q

Four numbers that describe a rotation. They only describe a rotation when their length is 1, so a reader scales them to length 1 first.

Footprint

The patch of the screen where one splat can add any color.

Jacobian J

The matrix of the projection's slopes at one point, used as a straight-line stand-in for the projection near the splat's center.

Opacity α , transmittance T

Opacity says how much a splat covers. Transmittance is how much of what lies behind still shows after the splats in front: the product of $(1 - \alpha)$ over them.

Alpha compositing

Laying colors over one another in order, each weighted by its opacity and by how much of the pixel is still uncovered.

Spherical harmonics

A compact way to store how a color changes with the direction you look from. Many trained captures store them; a kit splat has one base color.

Recipe, capture

A recipe is a program that makes splats. A capture is a file of splats fitted to photographs of a real thing.

u, v, t, morph

u and v are the two parameters each splat gets in the equation language. t is time: 0 to 2π in the equation language, and the toy's running time in a recipe's `drive`. A morph is a splat sliding from its own place to a target place.

Kernel

The rule for how a splat's weight falls off across its patch. The site normally draws a cut-off Gaussian; a labs setting can use a sharper one. Neither is the ideal bell.

Further reading

Five sources, each opened and checked on October 4, 2026. Authors, titles, venues and years are as the source's own page gives them.

- Bernhard Kerbl, Georgios Kopanas, Thomas Leimkühler and George Drettakis. **3D Gaussian Splatting for Real-Time Radiance Field Rendering**. SIGGRAPH 2023 (ACM Transactions on Graphics). [Project page](#) · [Paper](#). The starting point.
- Matthias Zwicker, Hanspeter Pfister, Jeroen van Baar and Markus Gross. **EWA Volume Splatting**. Proceedings of IEEE Visualization 2001. [Paper](#). The footprint step in Level 1.
- Zehao Yu, Anpei Chen, Binbin Huang, Torsten Sattler and Andreas Geiger. **Mip-Splatting: Alias-free 3D Gaussian Splatting**. CVPR 2024 (Oral, Best Student Paper). [Project page](#).
- Binbin Huang, Zehao Yu, Anpei Chen, Andreas Geiger and Shenghua Gao. **2D Gaussian Splatting for Geometrically Accurate Radiance Fields**. SIGGRAPH 2024. [Project page](#). A different method from Splashty's flat one-photo fit.
- Antoine Guédon and Vincent Lepetit. **SuGaR: Surface-Aligned Gaussian Splatting for Efficient 3D Mesh Reconstruction and High-Quality Mesh Rendering**. CVPR 2024. [Project page](#).

Quick reference

One splat

$$G(p) = \exp(-\frac{1}{2} (p - \mu)^T \Sigma^{-1} (p - \mu)), \quad \Sigma = R S S^T R^T$$

$$\Sigma' = J W \Sigma W^T J^T, \quad C \leftarrow a c + (1 - a) C \text{ (back to front)}$$

A splat program

```
x = ...      y = ...      z = ...      # in u, v and t (y is up)
u = 0 .. 2pi # ranges: numbers only
v = 0 .. pi  # default 0 .. 1
hue = ...    # 0 red, 1/3 green, 2/3 blue
r = ...      g = ...      b = ...      # or colors from 0 to 1
size = 0.05  # about the bell's  $\sigma$ 
count = 4000 # 100 to 10,000
spread = grid # or random
```

Functions: sin, cos, tan, asin, acos, atan, sinh, cosh, tanh, exp, log (ln), log10, sqrt, abs, floor, min, max. **Constants:** pi, e. **Time:** t runs from 0 to 2π per tap. At most 120 characters a field.

A picture toy

```
pictures: { sample: () => "assets/...", accept: ["pdf", "image", "gif", "video"] },
input: { title, media: { accept } },      // or placeholder, button, read, shown; or pad
tiltLock: true,                          // a drag turns it only left and right
build(k) { k.sheet({ id, center, width, height, leaf }); k.spine({ at, axis, dir }); },
drive(t, c, out, info) {
  out.sheets[id] = { page, visible };      // pages count from 0
  out.leaves[slot] = { angle, curl };      // radians; 0 flat, pi turned over
  info.data.pictures                        // page, count, go(n), next(), prev(), togglePlay()
}
```

The Tinkerer's Manual, first published September 28, 2026 and updated October 4, 2026. Part of [Splashery](#), a toy box of 3D Gaussian splats that runs in your browser. Every picture here was made with Splashery itself.